No: 11/45/2016-17-
GOVERNMENT OF INDIA
OFFICE OF THE DY. SUPERINTENDING HORTICULTURIST
ARCHAEOLOGICAL SURVEY OF INDIA
HORTICULTURE DIVISION NO: III,

Puratatva Bhavan, 2nd Floor, 4th Main 2nd Stage, Hebbal, Mysore - 17

NOTICE INVITING TENDER

On behalf of the President of India the Sealed Tenders are hereby invited from the approved/eligible Firms/Contractors from C.P.W.D./P.W.D/ Railway/P & T. Dept./Irrigation Dept. and other Govt./Semi-Govt. Dept. for the following works.

. Sl. No	Name of the works	Estimated Amount	E.M.D	Period of Completion	Last date & time of the sale of tender	Last date & time of the receipt of tender	Date & time of opening of tender
1.	Development of Garden at Mahadev Temple, Kurdi South Goa (GOA)	, 11,87,212	29,680	60 days from the date of award letter	21-03-2017 upto 17.00 hrs.	22-03-2017 upto 14.00 hrs.	22-03-2017 at 15.00 hrs.

The complete tender document can be downloaded from the departmental website www.asihorticulture.com, & www.asi.nic.in The tender document must be submitted along with the cost of tender document Rs.525/- (non-refundable), E.M.D. in shape of Demand Draft drawn in favor of Dy. Suptdg. Horticulturist, A.S.I., Hort. Divn. No.III, Mysore-17, self attested photocopies of Contractor's valid Registration Certificate experience of similar nature of work as per schedule attached in any Govt. / Semi Govt. organization (at least 80% of estimated tender amount) and income Tax Return filed for the last three years up to the specified date and time, failing which the tender will summarily rejected. No digital signature is required.

The tender will be opened in the presence of Contractors or their authorized representatives, if present, on the specified date and time. The sealed cover should be super scribed with the name of work and date of opening. The competent authority reserves all the right to accept / reject any or all the tender by recording sufficient valid reason thereof. The E.M.D. of unsuccessful bidder will be return in due course. If the date of receiving / opening of the tender happen to be holiday, the tender will be opened on the next working day.

Dy. Suptdg. Horticulturist
A.S.I., Hort. Divn. No. III, Mysore -17.

Endtt. No.11/45/2016-17- Date. 09-03-2017

Copy forwarded for information and wide publicity to :

1. The Director (Administration), A.S.I., Janpath, New Delhi.
.2. The Director (Horticulture), A.S.I., Mall Road, Agra.
3. Executive in-charge of the works.
4. The Notice Board, Hort. Divn. No.III, Mysore.

Dy. Suptdg. Horticulturist
A.S.I., Hort. Divn. No. III, Mysore -17.

TENDER SCHEDULE
A.S.I.W. - 29

Price of Tender form : Rs. 525/- **S.l. No:**

On behalf of President of India I/We hereby quoted item, rate Tender for Maintenance of garden as described in the under mentioned Memorandum according to the specification within the rates specified subject to the Terms & Conditions of the contract.

Name of the work : Development of Garden at Mahadev Temple, Kurdi South Goa (GOA)

Date of Receiving of Tender 22-03-2017 upto 14-00 hrs.
Date of Opening of Tender 22-03-2017 at 15-00 hrs.

MEMORANDUM

1. Earnest Money ₹ 29,680-00
2. Security Deposit ₹ 66,861-00
3. Estimated Tender Amount ₹ 11,87,212-00
4. Period of Completion : **Within 45 days from the issue of Award Letter /Supply order.**
5. Place of Work : Landscaping around St. Augustine Church, Archaeological Survey of India,Old Goa (GOA)

Sl. No	Details of works	Quantity	Rate	Per Unit	Amount
1	2	3	4	5	6
I	Area for Development---------	9021.1 m^2 2.23 acr			
II	Horticultural works (A) PREPARATION OF LAWN				
	(a) Trenching Trenching in ordinary soil up to a depth of 0.60m including removal and stacking of serviceable materials and then disposing of by spreading and neatly leveling with in a lead of 50 m and making up the trenched area to proper levels by filling with earth or earth mixed with sludge or/and manure before and after flooding trench with water (excluding cost of imported earth, sludge or manure).	1826 m3			
	(b) Supplying and stacking of good earth at site including royalty and carriage up to 1 km (earth measured in stacks will be reduced by 20% for payment).	228 m3			
	(c) Supplying and stacking of Neem Shield at site including royalty and carriage up to 1 km	153 kg			
	(d) Rough dressing the trenched ground including breaking clods.	3043 m^2			
	(e) Uprooting weeds from the trenched area after 10 to 15 days of its flooding with water including disposal of uprooted vegetation.	3043 m^2			
	(f) Fine dressing the ground	3043 m^2			

	(g) Spreading of sludge, dump manure or/and good earth in required thickness (Cost of sludge, dump manure or/and good earth to be paid separately).	228 m3			
	(h) Mixing earth and sludge or manure in proportion specified or directed.).	228 m3			
	(i). Grassing with selection No.1 grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn, free from weeds and fit for mowing including supplying good earth, if needed (the good earth shall bepaid for separately).	3043 m^2			
	(B) Preparation of Hedge, Shrubbery (a) Trenching Preparation of beds for hedging and shrubbery by excavating 60cm deep and trenching the excavated base to a further depth of 30cm, refilling the excavated earth after breaking clods and mixing with sludge or manure in the ratio of 8:1 (8 parts of stacked volume of earth after reduction by 20% one part of stacked volume of sludge or manure after reduction by 8%), flooding with water, filling with earth necessary, watering and finally fine dressing, leveling etc., including stacking and disposal of materials declared unserviceable and surplus earth by spreading and leveling as directed, within a lead of 50m lift up to 1.5m complete (cost of sludge, manure or extra earth to be paid for necessary).	149 m3			
	(b) (i) Supplying and stacking of good earth at site including royalty and carriage up to 1 km (earth measured in stacks will be reduced by 20% for payment).	44 m3			
	(c) Supplying and stacking of sludge at site including royalty and carriage up to 1 km (earth measured in stacks will be reduced by 8% for payment). DSR 2016, Page no.372, item no.23.3) Dung Manure N2 @ 5%	6 m3			
	(C) Tree Plantation				
	(i) Digging holes in ordinary soil and refilling the same with the excavated earth mixed with manure or sludge in the ratio of 2:1 by volume (2 parts of stacked volume of earth after reduction by 20% : one part of stacked volume of manure after reduction by 8%), flooding with water, dressing including removal of rubbish and surplus earth, if any with all leads and lifts (cost of manure, sludge or extra good earth if needed to be paid for separately) (Distance 8m X 8m apart)				
	(i) No. of tree plantation	110 Nos			
	(b) (i) Supplying and stacking of good earth at site including royalty and carriage up to 1 km (earth measured in stacks will be reduced by 20% for payment110nos X 3.14 X 0.60X0.60 X 1.20 = 149cum	100 m3			
	(c) Supplying and stacking of Manure at site including royalty and carriage up to 1 km (earth measured in stacks will be reduced by 8% for payment). Dung Manure N2 @ 5%	50 m3			

III	**(A) Sinking of 200 mm dia Bore well & providing submersible pump set alongwith accessories**				
	(i) Drilling charges	100 mtr			
	(ii) Providing of PVC 200mm dia casing pipe	20 mtr			
	(iii) Providing of 63mm dia HDPE pipe suction/delivery pipe (for submersible pump set)	100 mtr			
	(iv) Indoor panel box including preventer, strarter, indicator, cutouts wiring charges etc	1 job			
	(v) Outdoor panel box (size 3' X 2' X 1.5') with iron angle legs	1 job			
	(vi) Towards cost of 4sqmm flat cable from pump set to panel	125 mtr			
	(vii) Towards cost of 8 mm steel rope for handing pumpset in borewell	125 mtr			
	(B) Providing & laying of PVC pipes & Hydrants (i) Trenching Excavating trenches of required width for pipes, cables, etc, including excavation for sockets, and dressing of sites, ramming of bottoms, depth upto 1.5 m including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth including consolidating each deposited layer by ramming, watering, etc, and disposing of surplus excavated soil as directed, within a lead of 50 m:(DSR.2016,page no.78, item no.2.13.1)	375 mtr			
	(ii) Towards cost of 63mm rigid P.V.C pipe 6kg/cm2 pipe with ISI std& ISO- 4985 : 2000 (including wastage 30 mtrs) for distributory line	390 mtr			
	(iii) Towards cost of specials for pipe line	LS			
	(iv) Towards cost of QCV hydrants	20 Nos			
	(v) Towads payment of Laying charges	375 mtr			
	Total :				

Amount in words :

Signature of Contractor with full address and seal

Dy. Suptdg. Horticulturist,
ASI., Hort. Div. No: III, MYSORE-17.

Should this tender be accepted, I/We hereby abode by and and fulfill all the terms and conditions annexed hereto so far. As applicable, and /or in default to forfeit and pay of the President of India or his successor in office the sum of money mentioned in the said conditions. A sum of ₹ **……..** Is herewith forwarded in Demand Draft/Banker Cheque as earnest money, in the name of the Dy. Superintending Horticulturist, A.S.I., Horticulture Division No: III, Mysore -17, if I/We fail to commence the work, specified in the above Memorandum. If I/We fail to deposit the amount of security deposit specified in the above Memorandum in accordance with the clause of the said conditions of contract. I/We agree that the said President or his successors in office shall, without prejudice to any other right or remedy, shall be retained by his towards such security deposit. I/We further agree that the said President or his successors in office shall also be at liberty to cancel the acceptance of the tender if I/We fail to deposit security amount to aforesaid.

Issued to …….
……..
……..

Dy. Suptdg. Horticulturist,
ASI, Hort. Div. No: III, MYSORE-17.

Signature of Contractor with full address and seal
Date:

The above tender is hereby accepted by me for ……. (in words ……

…… ……

on behalf of the President of India.

Date:

Dy. Suptdg. Horticulturist,
ASI., Hort. Div. No: III, MYSORE-17.

Terms & Conditions attached.

TERMS AND CONDITIONS

1. The work shall be carried out by the contractor/ firm strictly and in accordance with A.S.I specifications as amended from time to time.
2. The normal working hours will be 8 hours a day from 8.00 A.M. to 5.00 P.M. wisth one hour lunch break from 12.00 Noon to 1.00 PM subject to staggering of duty hours as per actual requirement. The garden should maintain in presentable condition during the period mentioned in the award latter.
3. Contractor will follow the minimum wages act and liable to maintain the records of labour required under labour law.
4. The tender must accompany with the Earnest money of ₹ **29,680/-** in the form of Demand Draft in favor of "Dy. Superintending Horticulturist, A.S.I., H.D-III, Mysore." Cheque will not be accepted.
5. Rate should be quoted with all taxes, leads and lifts etc., Nothing extra should be paid over the rates quoted by the contractor/Firm.
6. The tender must accompany self attested photocopies of Contractor's valid Registration Certificate experience of similar nature of work as per schedule attached in any Govt. / Semi Govt. organization (at least 80% of estimated tender amount) and income Tax Return filed for the last three years.
7. The contractors / firm should not sublet any portion of contract.
8. The contractors / firm should comply the requirement of labour / child labour Act and they will be responsible for violation, if any.
9. The agreement can be closed at any time due to technical reasons or financial complications. In these circumstances no claim shall be made. Dept./ Govt. shall not pay any compensation on this account.
10. The running payment will be made as per rules of A.S.I.
11. Security Money will be deposited in advance by the contractor / firm whose tender is accepted by the competent authority.
12. The contractor will have to make necessary arrangements for clean drinking water, housing, medical facilities and other necessary welfare measures for the labourers engaged for the work at his own expenses.
13. The Earnest Money and Security deposit of the successful contractor / firm will be forfeited, if he fails to comply with any of the conditions of the contract and work shall be carried out at risk and cost of the contractor / firm.
14. The department will not be held responsible for any incident occurred with labours engaged by the contractor for work and no compensation will be paid by the department for the same.
15. The contractor will be held responsible for loss of Govt. property due to negligence of watch and ward and same will be replaced by him at his own cost.
16. The Contractor should apply the fertilizer/manure/plant protection materials as and when required as per the directions of the Dy. S.H. A.S.I., H.D-III, Mysore , or his representative.
17. Contractor has no right to make any amendment in the existing landscaping of the garden.
18. The department has full right to make any amendment in the existing landscaping of the garden.
19. The undersigned reserves the right to terminate the tender at any time after serving 15 days notice.
20. The payment will be released to the contractor by furnishing the bill after a certification from the concerned Executive Assistant.
21. Other terms and conditions will be same as are prescribed for contract work.
22. The contractor will be responsible for loss/deliberated damage of any equipment/installation at site.
23. The day to day work will be started as per the instruction of the Dy.S.H. A.S.I., H.D-III, Mysore, or his representative.
24. Contractor will be responsible for damage of the garden/plants by stray cattle and unauthorised wood cutters.
25. The contract is subject to availability of funds, if funds are exhausted, then tender can be terminated at any time after serving 15 days notice.
26. Garbage, waste materials of the garden should be thrown out side the garden or as directed by the local in charge officer.
27. Good earth suitable for cultivation onl need be supplied. The soil should neither be alkaline nor acidic in nature. The PH value of good earth should be between 6.7 & 7.5. The earth should be rich in nitrogenous contents & humus. The good earth supplied should be free of weeds and clods.
28. Soil testing has to be done before the supply of good earth. The sample of good earth required for testing, shall be supplied free of charge by the contractor/firm. Conveyance, packing etc, of sample shall be borne by the contractor/firm. The soil sample shall be tested only in the Govt. soil testing laboratory.
29. Sample of good earth to the tune of 3 to 4 truck loads should be supplied by the contractors and should be stacked at the site shown near the garden. Approval of tender should be subjected to approval of the sample good earth and Dung Manure. This sample good earth should be preserved till the end. Check measurements of the stacks should be done in the presence of undersigned or deputed person.
30. Each stack should be made of at least 3 to 4 loads of good earth and Dung Manure.
31. Stocked volume will be reduced by 20% for voids for payment of good earth supplied. And 8% for voids for payment of Dung Manure,
32. PVC pipes, Good earth, Dung Manure etc., Supply should be on as per **"supply at site**" basis.
33. Overall rates shall be considered for approval of tender.

NOTE: THE MAINTAINANCE OF GARDENS SHOULD BE STRICTLY UNDER THE DIRECTIONS OF DEPUTY SUPERINTENDING HORTICULTURIST, ARCHAEOLOGICAL SURVEY OF INDIA, MYSORE OR HIS REPRESENTATIVES.

Accepted

(Signature of Contractor) Dy. SUPTDG. HORTICULTURIST