F. No.M3/SK/02/2016-17
Government of India
Office of the Superintending Archaeologist
Archaeological Survey of India
Kolkata circle, C.G.O. complex (4th floor)
Block-DF, Sector-I, Salt Lake City,
Kolkata – 700 064.
Web Site : www.asi.nic.in / www.asikolkata.in

Dated:

LIMITED TENDER NOTICE

Name of the Work: Execution of works under S.R(Plan to reparing of Plinth protection of Coronation throne at Norbugang under Geyzing Sub Circle for 2016-17').

The Superintending Archaeologist, Archaeological Survey of India, Kolkata Circle, Kolkata, on behalf of the President of India invites item rate tender in sealed cover from the approved contractors/suppliers who have past experience of successfully completing similar execution of works at **Coronation throne at Norbugang under Geyzing Sub-Circle** as per detailed below up-to 15.00 hours on **24.02.2017** which will be opened on the same day at 15.30 hours in the Office of the Superintending Archaeologist, Archaeological Survey of India, Kolkata Circle, C.G.O. Complex (4th floor), Block-DF, Sector-I, Salt Lake City, Kolkata–700064.

LIMITED TENDER NOTICE

S.No.	Details of item	Quantity	Rate
1.	Cleaning the fallen ancient stone compound wall by ordinary labour	**14.94 sq.m**	**Per sq.m.**
2.	Restoration of fallen portion of compound wall with mortar (1:1:4)	**11.95 cum**	**Per cum**
3.	Dismantling of old plinth protection of drain of the Puja Griha near Lama kitchen(octagonal)	**2.48 cum**	**Per cum**
4.	Laying in position cement concrete of specified grade excluding the cost of centering and shuttering all works of base of plinth protection 1:2:4	**4.69cum**	**Per cum**
5.	Laying of stone (RR) at the plinth protection at the Puja Griha near Lama kitchen with (1:6)mortar	**4.69cum**	**Per cum**
6.	Plastering the drain (12mm) in fron of Puja Griha adjacent to plinth protection near Lama Kitchen with mortar (1:6) complete	**13.76 sq.m**	**Per sq.m**
7.	Pointing the ancient stone compound wall and existing stone pathway with mortar(1:4) including raking out the joints and preparing the surface of re pointing(flush/ruled pointing)	**1739.35sq.m**	**Per sq.m**
8.	Applying two coats of water based repellent to the Stupa in front of the Coronation throne to protect from ingress of rain water	**Whole job**	**Whole job**
9.	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give as ever shade.	**159.20 sq.mtr.**	**Per sq.m**
10.	Fitting and fixing of sanitary fittings at the toilet of Coronation throne. Indian Pan: 2 Nos. Cistern: 2 Nos. Connection pipe: 2 Nos. Stop cock: 2 Nos. Bib Cock (steel) 3 Nos.	**Whole item**	**Whole item**
11.	Rewriting the cultural and Direction & Notice Board	**2 Nos.**	**Per No.**

*** Prior experience of similar execution of work for Heritage Building status and specific to the items entered above within two (2) years are pre-requisite of the applicant/ tender, without which the tender papers will not be issued.**

Tender of the contractors/suppliers who will not deposit earnest money **Rs.10,273/- (Rupees Ten thousand two hundred and seventy three Only) vide Demand Draft from any Nationalized Bank in favour of the "Superintending Archaeologist, Archaeological Survey of India, Kolkata circle, Kolkata"** and copies of the Registration Certificate and latest Income tax clearance

certificate/Vat clearance certificate as per notification of Directorate of commercial taxes, West Bengal vide no. 1290 F.T. dated 31.07.2006 shall be summarily rejected.

The competent authority reserves the right to accept or reject any or all tenders without assigning any reasons thereof. Conditions & Tender Forms can be obtained from the office of the Superintending Archaeologist, Archaeological Survey of India, Kolkata Circle, Kolkata between 10.00 to 16.00 hours on all working days on payment of **Rs.500/-(Rupees Five hundred only)** (non-refundable) **upto 22.02.2017.** Last date of application for **tender form** **21.02.2017.**

In case of public holiday declared on the opening date Tender the same would be opened on the next working day.

CONTRACTORS/SUPPLIERS MUST SUBMIT THE TENDERS DIRECTLY TO THIS OFFICE IN PERSONS OR BY POST WITHIN THE STIPULATED DATE.

Execution of work should be completed within **25** days from the date of issue of work order.

The tender form can be downloaded from website www.asikolkata.in/www.asi.nic.in/www.eprocure.gov.in. All tender forms downloaded from the Website shall be accepted only if the tender form cost is remitted while submitting the tenders.

15/2/17

Superintending Archaeologist (i/c)

F. No.M3/SK/02/2016-17 – 3895.

Dated : 15 FEB 2017

To

1. OFFICE NOTICE BOARD, A.S.I., Kolkata Circle, Kolkata.
2. Office Notice Board, A.S.I., Geyzing Sub Circle, Koch Behar.
3. The Web Manager, A.S.I., New Delhi.
4. Shri Pankaj Kumar Das, Senior C.A., Geyzing sub circle.
5. Office Copy.