



प्रत्नकीर्तिमपावृणु

No. 2/37-W/2016-17
Government of India
Archaeological Survey of India
Guwahati Circle
Office of the Superintending Archaeologist
G.N.B.Road, Ambari, Guwahati – 1

Dated, the

NOTICE INVITING TENDER

The Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati on behalf of the President of India invites Tender in sealed cover from the Contractors approved & registered by CPWD/PWD/MES/Railways and other Govt./Semi Govt. Department with valid license including valid PAN & VAT Reg. No. (GRN) **having experience in works with Archaeological Survey of India for execution of work & supply of materials as per specification.** The tender document will be issued on written request upto 05.00 hrs. on **14.03.2017** and the tender document will be received up to 14.30 hours on **15.03.2017** and the same will be opened on the same day at 15.00 hours in presence of intending tender bidders or their authorized representatives.

Name of work	Estimated cost	Date of opening	Remarks
Replacement of roofing and Showcase, installing fan, painting etc. at Sri Suryapahar Museum for 2016-2017	₹ 3,19,193/-	15/03/2017	Execution of work and supply of materials as per specification

Tender documents is also available in the Departmental website www.asi.nic.in and www.asiguwahaticircle.gov.in and also on central public procurement portal www.eprocure.gov.in which may be downloaded and should be submitted duly filled along with the earnest money of ₹ 7,980/- only and cost of tender form of ₹ 500/- only (non-refundable) separately in the form of Demand Draft of any Nationalized Bank obtained in favour of the “Superintending Archaeologist, Archaeological Survey of India, Guwahati Circle, Guwahati - 1” including Contractor’s Registration certificate, PAN, VAT clearance certificate, Labour registration, work order/experience certificate of similar works etc. failing which the tender will summarily be rejected. The EMD of unsuccessful tender bidders will be returned in due course.

The undersigned reserves the right to accept or reject any or all the tenders without assigning any reasons thereof. Any type of information regarding this tender may be obtained from this office on all working days. The contractors will have to quote the rate of all items mentioned in the tender schedule failing which the submitted tender will be rejected.

The WCT VAT, Income Tax & Labour-cess at prescribed rate will be deducted from the total billed amount at source during payment.


Superintending Archaeologist

No. 2/37-W/2016-17-5415

Dated **6-9 MAR 2017**

Copy forwarded with the request to exhibit in the office Notice Board for wide publicity :

1. The Additional Director General, ASI, ND for hosting of NIT on the Central Public Procurement Portal (www.eprocure.gov.in)
2. The Dy. Commissioner, Dist. Goalpara
3. The Executive Engineer, PWD, Dist. Goalpara
4. The Sr. Conservation Assistant, ASI, Guwahati Sub Circle.
5. Guwahati Circle Office Notice Board.
6. Website section of Guwahati Circle, Guwahati.
- ✓ 7. The Web Manager, ASI, Janpath, ND to upload in the website “www.asi.nic.in”


Superintending Archaeologist

Price of Tender ₹ 500/-

TENDER FOR EXECUTION OF WORK

I/we hereby tender for execution of work on behalf of the President of India as described in the under mentioned memorandum according to the specification within the times specified and the rates specified therein subject to the conditions of the contract for execution of work for **Replacement of roofing and Showcase, installing fan, painting etc. at Sri Suryapahar Museum for 2016-2017.**

Memorandum :-

- i) Earnest Money : ₹ 7,980 /-
- (ii) Security Deposit : ₹ 31,919/-
Estimated Cost : ₹ 3,19,193/-
- a) Payable immediately on the acceptance of tender (including earnest money if deposited in cash with tender)
- b) Percentage to be deducted from bill

Demand Draft No.
made up as under :

As admissible ₹

Schedule of Quantities of work

Date of opening of Tender : 15/03/2017.

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)
Item No.	Description or specification of work to be executed	Total Quantities of each to be executed	Places at which to be Executed	Quantities of work to be executed at each place	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer) ₹	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer) ₹	Remarks
1.	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of : G.S. Sheet.	31.08 SqM	Work at site	Work at site	Work to be completed by _____ days		Per SqM		Tender items S/No. 1 to 13 in Schedule is a single unit of Tender. No split up of items is entertained.
2	Providing corrugated G.S. sheet roofing including vertical/curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two	31.08 SqM	-Do-	-Do-	-Do-		Per SqM		Do

(Signature)
Sri Arun Kumar
Superintending Archaeologist
Archaeological Survey of India
Gawahati

	coats of approved paint on overla- pping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275gm/m ²									
3	Supply Two Nos. ceiling fan including fitting & fixing of the ceiling fan in the museum office building with transportation, testing & installing etc. all complete. (ISI Mark)	Whole work	-Do-	-Do-	-Do-	-Do-		Whole work		-Do-
4	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required.	1 No	-Do-	-Do-	-Do-	-Do-		Per No		-Do-
5	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350mm and 340x410x265mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required One urinal basin with 5 litre white P.V.C. automatic flushing cistern.	1 No	-Do-	-Do-	-Do-	-Do-		Per No		-Do-

6	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require.	1 No	-Do-	-Do-	-Do-	-Do-	Per No	-Do-
7	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing Circular shape 450mm dia.	1 No	-Do-	-Do-	-Do-	-Do-	Per No	-Do-
8	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge.	Whole item	-Do-	-Do-	-Do-	-Do-	Whole	-Do-

1. 50 mm nominal outer dia pipes. 5.00 m
2. 25 mm nominal outer dia pipes. 10.00 m
3. 40 mm nominal outer dia pipes. 10.00 m
4. 100 mm nominal outer dia pipes. 5.00 m
5. P. V. C. connection pipe 45 cm long. 3 nos.
6. Brass full way valve 50 mm dia. 2 nos.
7. Pillar cock (fancy) 15 mm foam flow. 2 nos.
8. C. P. Brass long nose bibcock 15 mm. 2 nos

9	Provision for replacement of two showcases as previous type (size 0.65x0.40x2.55 & 2.46x0.40x2.55) and painting of heritage plaster on new showcases.	Whole item	-Do-	-Do-	-Do-	Whole	-Do-
10	<ol style="list-style-type: none"> 1. Water proof 90 mm thick play board. 20 sqm. 2. Water proof 6 mm thick play board. 10 sqm. 3. Sun maker 2 pic. 4. Dendrite. 4 ltrs. 5. Fevicol 3 ltrs. 6. Nails 2": 3 Kg. 7. Nails 1.5": 2 Kg. 8. Nails 2": 2 Kg. 9. Pin Nails. 1 kg. 10. Plastic gutka 1 pkt. 11. LED light & sock (1 wt) 35 nos. 12. LED light & sock (3 wt) 30 nos. 13. Connecting wire 2 coil. 14. Old showcase dismantling charge. 15. Fiting, fixing & making charge. 16. Fiting the electric connection. 17. Liquid erkilty putty. 3 ltrs. 18. Wood primer. 5 lits. 19. Heritage plaster. 4 bag. 20. C.M.C Medicine. 21. Borning 2 gallon. 22. Red oxide 1.50 kg. 23. 4" brush. 3 nos. 24. Terpin oil, 4.5 ltr. 	472.20 SqM	-Do-	-Do-	-Do-	Per SqM	-Do-

