

**Government of India
Archaeological Survey of India
Bangalore circle, Bangalore**

TENDER NOTICE

File No. 64/07/106/2016-17/Cons

Date:

The Superintending Archaeologist Archaeological survey of India Bangalore circle Bangalore on behalf of president of India invites item rate tender in sealed cover for the below mentioned works as per specification in the tender schedule from the approved registered contractors of Archaeological Survey of India and Bangalore circle on **up to 21.11.2016 15.00hrs** which will be opened in the office of the Superintending Archaeologist, Archaeological survey of India Bangalore circle at **15:30** hrs on the same day. The intended firms/ contractors should invariably submit the registration, experience and other related certificates along with the tender schedules.

Name of work

OW (P) to Up-gradation of Ticket counter at Somanathapura

Est. Amount: Rs.3,89,481/-

EMD: Rs.9,740/-

Execution to work

The earnest money should be deposited in the form of Demand draft from any nationalized bank obtained in favour of the Superintending Archaeologist, Archaeological Survey of India, Bangalore Circle, Bangalore.

The tenders of those firms who do not deposit earnest money will be summarily rejected. Tender forms and conditions can be had from this Office on or before **18.11.2016** on all working days in Office hours on payment/ demand draft of Rs.500/- drawn in favour of "Superintending Archaeologist, Archaeological Survey of India, Bangalore circle, Bangalore + 14.5% tax drawn in favour of "ACCT LVO -15, Bangalore" from any Nationalized bank along with the **EMD** towards the cost of tender Schedule.

Address for the Sale of tender document

**The Jr.Conservation Assistant
Archaeological Survey of India,
Purathathva Bhavana,
Near Sankranthi Circle,
Hebbala Ind Stage,
Mysore – 570 017.**

**The Superintending Archaeologist,
Archaeological Survey of India
Bangalore Circle 5th floor 'F' wing
Kendriya sadan Koramangala
Bangalore –34**

Sd/-

Superintending Archaeologist

Copy to:

1. To Jr.Conservation Assistant, A.S.I, Mysore, for information and necessary action.
2. All Contractors of Bangalore Circle

For Superintending Archaeologist

Schedule

Name of Work: OW (P) to Up-gradation of Ticket counter at Somanathapura

T.NO / 2016-17

Sl. No	Description	Quantity	Rate	Amount
1	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50m after breaking of clods complete as per specifications	19.80 Cum		
2	Providing and filling sand and boulder for foundation	6.32 Cum		
3	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15cms, thick well compacted, in foundation including cost all materials, labour, HOM of machinery, curing complete as per specifications.	2.10 Cum		
4	Providing and constructing granite/ trap/ basalt size stone masonry in foundation with cement mortar 1:6, stone hammerdressed in courses not less than 20cms high, bond stones at two m. apart in each course including cost of materials, labour curing complete as per specification	10.08 Cum		
5	Filling available excavated earth (excluding rock) in sides of foundations up to plinth in layers not exceeding 20cms. in depth, compacting each deposited layer by ramming after watering with lead up to 50m. and lift up to 1.5m. Including cost of all labour complete as per specifications.	29.23 Cum		
6	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.70cum and fine aggregates @ 0.47cum with super plastisiser @ 3lts conforming to IS9103-1999 Reaffirmed-2008, machine mixed concrete laid in layers not exceeding 15cms thick, vibrated	5.80 Cum		

	for all works in ground floor level for roof slabs, staircase, lintels and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all Materials, labour, HOM of machinery, curing complete but excluding cost of reinforcement as per specifications. (Excluding cost of steel, fabrication and finishing charges)			
7	Providing and removing centering, shuttering, strutting, propping etc., and removal of form of work for columns, pillars, post and struts, circular or curved in plan including cost of all materials, labour complete as per specifications.	29.92 Sqm		
8	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications	8.40 Sqm		
9	Providing and constructing Solid cement block masonry for basement and superstructure with approved quality of standard size of class designation 3.5Newton per sqm with cement mortar 1:6 including cost of materials, labour charges, scaffolding, curing complete as per specifications. (400mm x 200mm x 200mm)	38.56 Sqm		
10	Providing HYSD steel (cold, twisted) reinforcement for RCC work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastages shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (KBS 4.6.3) lift charges for steel of all diameters for additional floors over ground floor per quintal floor height of 3.50m or part there of cost of labour complete as per specification.	0.58 Mt		
11	Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering. : Providing and removing scaffolding, including cost of materials, labor, curing complete as per specifications. (inside walls)	46.82 Sqm		

12	Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering. : Providing and removing scaffolding, including cost of materials, labor, curing complete as per specifications. (outside walls)	42.62 Sqm		
13	Providing lime rendering for plastering to walls & ceilings , including cost of materials, labour, curing, complete as per specifications	70.94 Sqm		
14	Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brooming the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications.	250.68 Sqm		
15	Providing and finishing external walls in two coats with water proof cement paint of approved brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.	138.35 Sqm		
			Total	

Conditions: -

1. The work should be completed within **90 days (Ninety days)** from the date of issue of written order to commence the work.
2. The work should be done to the complete satisfaction of the officer in charge.
3. The contractor should take particular care to see that no damage is caused to any part of the monument while executing the work.

For **Superintending Archaeologist**

I agree to abide by the above conditions and quote the rate to the estimated cost. Should the tender be accepted, I hereby agree to abide by and fulfill all the conditions and specifications contained in the CPWD pamphlet No.8 and general instructions and condition of contract which have been read by me or in default thereof to forfeit and pay to the President of India or his successors, the penalty of sum of money mentioned in the said conditions.

Contractor

Issued to :-

ITEM RATE - TENDER FOR WORKS PWD: 8

I/We hereby tender for the execution for President of India of the work specified in the under written memorandum within the time specified in such memorandum at the rates entered in the schedules mentioned in Rule 1 and in accordance in all respects with the specifications, designs, drawings and instruction in writing referred to Rule 1 here of & in clause 11 of the conditions of contract, and with such materials as are provided for by and in all other respects in accordance with such conditions so far as applicable .

Tender Form No. / 2016-17

MEMORANDUM

- | | |
|--|---|
| a) General Description | : OW (P) to Up-gradation of Ticket Counter at Somanathapura. |
| b) Estimated Cost | : Rs. 3,89,481/- |
| c) Earnest Money | : Rs. 9,740/- |
| d) Security Deposit
(including Earnest Money) | : Nil |
| e) Percentage, if any, to be
deducted from bill | : Nil |
| f) Time allowed for the work from date of
written order to commence | : 90 days |

Should this tender be accepted, I / We hereby agree to abide by and fulfill all the terms and provisions of the conditions in the pamphlet names 'General Conditions and Instruction of Contract' which have been read by me / read and explained to me so far as applicable or in default thereof to forfeit and pay to the President of India or his successors in office the same sum of money mentioned in the said conditions.

The Sum of Rs. _____

Is herewith forwarded in currency notes as earnest money the full value of which is to be absolutely forfeited to the said President or his successors in office, without prejudice or to any other rights or remedies of the said President or his successors in office, should I / We fail to commence the work specified in the above memorandum , @ (a) should I/We not deposit the full amount of security deposit specified in the above memorandum, in accordance with the clause(I) (A)of the said conditions of contract , otherwise the said sum of Rs. _____ shall be retained by Government as on account of such security deposit as aforesaid : or (b)the full value of which shall be retained by the Government on account of security in Clause (I) (B) of the said conditions, of contract.

In figures as well as in words

(a) If several sub works are included they should be detailed in a separate list
Give particulars and numbers

@ Strikes out (a) if no cash security deposit is to be taken.

Strike out (b) if any cash security deposit is to be taken.

Dated the _____ day of _____ 200

Witness:

Signature of contractor
Before submission of tender

Address:

Occupation

Signature of Witness to
Contractor Signature

The tender is hereby accepted by me on behalf of the President of India.

Dated the _____ day of _____ 200

Schedule showing (Approximately) materials to be supplied by the Public Works Department under clause (10) and (25) of the conditions of contractor for work contracted to be executed and the rates at which they are to be charged for:

Particulars	Rates at which the materials will be charged to the Contractor	Palace of Delivery
{ NIL	Unit	Rs. NIL }

Note : The _____ or firm submitted the tender should see that the rates in the above schedule are filled up by the Engineer –in – charge on the issue of the form prior to the submission of the tender.

Signature
Contractor

Signature

Sub-divisional Officer
Divisional Officer